



JAGIELLONIAN UNIVERSITY
IN KRAKOW



SOLARIS
NATIONAL SYNCHROTRON
RADIATION CENTRE



JAGIELLONIAN UNIVERSITY
IN KRAKOW



SOLARIS
NATIONAL SYNCHROTRON
RADIATION CENTRE

Solaris Status

Adriana Wawrzyniak

On behalf of Machine Group

National Synchrotron Radiation Center SOLARIS



Kraków, 27.11.18

Outline

- Introduction
- Operation in 2018
- Machine failures
- Machine upgrades & improvements
- Summary




600 MeV Linac with RF Thermionic Gun
1.5 GeV Storage Ring
2 operating beamlines



Parameter	Designed	Measured
Electron energy	1.5 GeV	1.45 ±0.5 GeV
Max. current	500 mA	500 mA/ operation @280mA
Number of circulating bunches	32	30-32
Natural bunch length σ_z/w . Landau Cavities	14.2 /60 mm	-
Natural emittance (bare lattice)	5.982 nmrad	8.05 nmrad (±30%)
Coupling	1 %	0.86%
Energy spread (bare lattice)	0.000745	-
Tunes ν_x, ν_y	11.22, 3.15	11.22, 3.15
Natural chromaticities ξ_x, ξ_y	-22.96, -17.14	-
Corrected chromaticities ξ_x, ξ_y	+2,+2 ; +1, +1	+1.4, +1.6;+0.9,+0.9
Momentum compaction	3.055×10^{-3}	-
Energy loss/turn	114.1 keV	103.7 ±12.3 keV
Momentum acceptance	4%	3.7± (0.3)%
Synchronous phase	168°	167.4° ± 2.7°
Synchrotron tune	0.00239	0.00228
Physical acceptance h/v	18 /4 mmrad	15.68/3.77 mmrad
Total lifetime	13 h	8 h

PLANS FOR NEXT BEAMLINES



Operation Calendar 2018/2019

FIRST USERS on October, 1st

Aug 2018	Sep 2018	Oct 2018	Nov 2018	Dec 2018	Jan 2019	Feb 2019	Mar 2019	Apr 2019	May 2019	Jun 2019	Jul 2019	Aug 2019
##### Thu 02 Fri 03 Sat 04 Sun 05 ##### Tue 07 ##### Thu 09 Fri 10 Sat 11 Sun 12 ##### Tue 14 ##### Thu 16 Fri 17 Sat 18 Sun 19 ##### Tue 21 ##### Thu 23 Fri 24 Sat 25 Sun 26 ##### Tue 28 ##### Thu 30 Fri 31	Sat 01 Sun 02 M Tue 04 C C ##### Thu 06 C C Fri 07 B B Sat 08 Sun 09 M Tue 11 B B ##### Thu 13 B B Sat 15 Sun 16 M Tue 18 B B ##### Thu 20 B B Sat 22 Sun 23 M Tue 25 B B ##### Thu 27 B B Sat 29 Sun 30 M	##### Tue 02 B B Fri 05 B B ##### Tue 06 C C ##### Thu 08 B B Sat 10 Sun 11 M Tue 13 B B ##### Thu 15 B B Sat 17 Sun 18 M Tue 20 B B ##### Thu 22 B B Sat 24 Sun 25 M Tue 27 B B ##### Thu 29 B B Sat 31	Thu 01 Fri 02 M Sun 04 M ##### Tue 06 C C ##### Thu 08 B B Sat 10 Sun 11 M Tue 13 B B ##### Thu 15 B B Sat 17 Sun 18 M Tue 20 B B ##### Thu 22 B B Sat 24 Sun 25 M Tue 27 B B ##### Thu 29 B B Sat 31	Sat 01 Sun 02 M Tue 04 B B ##### Thu 06 B B Sat 08 Sun 09 M Tue 11 B B ##### Thu 13 B B Sat 15 Sun 16 M Tue 18 B B ##### Thu 20 B B Sat 22 Sun 23 M Tue 25 B B ##### Thu 27 B B Sat 29 Sun 30 M	Tue 01 ##### Thu 03 s s s Fri 04 s s s Sat 05 s s s Sun 06 s s s Tue 08 s s s Fri 09 s s s Sat 10 s s s Sun 11 s s s Tue 13 s s s Fri 14 s s s Sat 15 s s s Sun 16 s s s Tue 18 s s s Fri 19 s s s Sat 20 s s s Sun 21 s s s Tue 22 s s s Fri 23 s s s Sat 24 s s s Sun 25 s s s Tue 27 s s s Fri 28 s s s Sat 29 s s s Sun 30 s s s Thu 31 M	Fri 01 M Sat 02 s s s Sun 03 s s s C C ##### Tue 05 C C ##### Thu 07 B B Sat 09 B B Sun 10 s s s M ##### Tue 12 B B ##### Thu 14 B B Sat 16 s s s Sun 17 s s s M ##### Tue 19 B B ##### Thu 21 B B Sat 23 s s s Sun 24 s s s M ##### Tue 26 B B ##### Thu 28 B B Fri 29 B B Sat 30 s s s Sun 31 s s s	Fri 01 B B ##### M Tue 04 B B Fri 05 B B Sat 06 s s s Sun 07 s s s M ##### Tue 11 B B ##### Fri 12 B B Sat 13 s s s Sun 14 s s s M ##### Tue 18 B B ##### Fri 19 B B Sat 20 s s s Sun 21 s s s M ##### Tue 26 B B ##### Fri 28 B B Sat 29 s s s Sun 30 s s s Fri 31 B B	##### Sat 01 s s s Sun 02 s s s Fri 03 s s s Sat 04 s s s Sun 05 s s s ##### Tue 07 s s s Fri 09 s s s Sat 10 s s s Sun 11 s s s M ##### Tue 13 B B Sat 15 M ##### Tue 18 B B ##### Fri 19 M ##### Tue 21 C C ##### Thu 23 B B Fri 24 B B Sat 25 s s s Sun 26 s s s M ##### Tue 28 B B ##### Fri 29 B B Sat 30 B B Fri 31 B B	Sat 01 M Thu 01 s s s Fri 02 s s s M ##### Tue 04 B B ##### Thu 06 B B ##### Tue 08 B B ##### Thu 10 M ##### Tue 12 B B ##### Thu 14 B B Sat 15 M ##### Tue 18 B B ##### Fri 19 M ##### Tue 21 C C ##### Thu 23 B B Fri 24 B B Sat 25 s s s Sun 26 s s s M ##### Tue 28 B B ##### Fri 29 B B Sat 30 B B Fri 31 B B	##### M Thu 01 s s s Fri 02 s s s M ##### Tue 04 B B ##### Thu 06 B B ##### Tue 08 B B ##### Thu 10 M ##### Tue 12 B B ##### Thu 14 B B Sat 15 M ##### Tue 18 B B ##### Fri 19 M ##### Tue 21 C C ##### Thu 23 B B Fri 24 B B Sat 25 s s s Sun 26 s s s M ##### Tue 28 B B ##### Fri 29 B B Sat 30 B B Fri 31 B B		



Shifts organisation


- ❖ 2 Shifts from Tue to Fri
 - ❖ 2 operators on shift
 - ❖ 1st shift 8:00 -16:00; 2nd shift 14:00-22:00 by September
 - ❖ From October shifts 7:00-15:00; 14:00-22:00
 - ❖ 3 Injection per day 7:00; 14:00; 21:00
 - ❖ On call duties and extra hours during night shifts and Saturdays extra payed for operators and technical support
-
- ❖ 7 trained operators – operators are the machine and technical group members.
 - ❖ Plan to increase the number of operators. Train beamline scientists (5 people)
 - ❖ Increase employment in the machine group – open positions for Physicists, diagnostics spec., RF spec.; vacuum spec. and technician



Operation Calendar in 2018

2018			
Week			Operation mode
1	2018-01-01	2018-01-07	Shutdown
2	2018-01-08	2018-01-14	Shutdown
3	2018-01-15	2018-01-21	Shutdown
4	2018-01-22	2018-01-28	Machine dedicated time/start up
5	2018-01-29	2018-02-04	Beamline commissioning
6	2018-02-05	2018-02-11	Beamline commissioning
7	2018-02-12	2018-02-18	Beamline commissioning
8	2018-02-19	2018-02-25	Beamline commissioning
9	2018-02-26	2018-03-04	Beamline commissioning
10	2018-03-05	2018-03-11	Shutdown
11	2018-03-12	2018-03-18	Machine dedicated time
12	2018-03-19	2018-03-25	Beamline commissioning
13	2018-03-26	2018-04-01	Beamline commissioning
14	2018-04-02	2018-04-08	Beamline commissioning
15	2018-04-09	2018-04-15	Beamline commissioning
16	2018-04-16	2018-04-22	Shutdown
17	2018-04-23	2018-04-29	Shutdown
18	2018-04-30	2018-05-06	Shutdown
19	2018-05-07	2018-05-13	Machine dedicated time
20	2018-05-14	2018-05-20	Machine/ Beamline commissioning
21	2018-05-21	2018-05-27	Beamline commissioning /FUO
22	2018-05-28	2018-06-03	Beamline commissioning /FUO
23	2018-06-04	2018-06-10	Beamline commissioning /FUO
24	2018-06-11	2018-06-17	Beamline commissioning /FUO
25	2018-06-18	2018-06-24	Beamline commissioning /FUO
26	2018-06-25	2018-07-01	Beamline commissioning /FUO
27	2018-07-02	2018-07-08	Beamline commissioning /FUO
28	2018-07-09	2018-07-15	Beamline commissioning /FUO
29	2018-07-16	2018-07-22	Beamline commissioning /FUO
30	2018-07-23	2018-07-29	Shutdown
31	2018-07-30	2018-08-05	Shutdown
32	2018-08-06	2018-08-12	Shutdown
33	2018-08-13	2018-08-19	Shutdown
34	2018-08-20	2018-08-26	Shutdown
35	2018-08-27	2018-09-02	Machine dedicated time/start up
36	2018-09-03	2018-09-09	User operation
37	2018-09-10	2018-09-16	User operation
38	2018-09-17	2018-09-23	User operation
39	2018-09-24	2018-09-30	User operation
40	2018-10-01	2018-10-07	User operation
41	2018-10-08	2018-10-14	User operation
42	2018-10-15	2018-10-21	User operation
43	2018-10-22	2018-10-28	Shutdown
44	2018-10-29	2018-11-04	Machine dedicated time
45	2018-11-05	2018-11-11	User operation
46	2018-11-12	2018-11-18	User operation
47	2018-11-19	2018-11-25	User operation
48	2018-11-26	2018-12-02	User operation
49	2018-12-03	2018-12-09	User operation
50	2018-12-10	2018-12-16	User operation
51	2018-12-17	2018-12-23	Shutdown
52	2018-12-24	2018-12-30	Shutdown

OPERATION working hours




1503 h scheduled for BL by the end of 2018

By today

	Scheduled	Used
TOTAL HOURS BL	1236	1118,3
TOTAL HOURS MC	360	359,7


2018	Availability[%]	MTBF[h]	MTTR [h]	Av I [mA]
October	97.2	19.1	0.9	250
November	99.6	73.3	0.3	262
2018	91.4	18.6	1.5	

MACHINE FAILURES



Main failures

- ☹ Diagnostic trips due to libera suspension in March
- ☹ Vacuum trips due to malfunction of the VK2 March-April
- ☹ Correctors connection burn
- ☹ Semiinstrument PS –current drops during ramping [solved]
- ☹ Water interlocks
- ☹ RF – LLRF phase stabilization, plungers in LC




Failure CODE List	
B	Beamlines
CT	Controls
DIA	Diagnostics
MPS	MPS interlock
ID	Insertion Devices
INF	Infrastructure
I	Linac
MML	High Level Software (MML)
HE	Human error
OI	Orbit Interlock
OT	Others
NET	Network
MAG	Supplies
PSS	PSS (except BLs)
RF	Radio Frequency
VAC	Vacuum
WAT	Water interlocks

Replacement of the dipole vacuum chamber in sector R1-02

- An abnormal value of heat was detected at the exit of the vacuum chamber by thermocouple connected in the vicinity of crotch absorber (CROD) and RF shielding.
- During visual inspection the shape of the RF shield was found out of the specification due to, as we think, a huge thermal load caused by synchrotron radiation.
- Since the vacuum performance of this chamber stood out clearly from the others vacuum chambers mounted in DBA's it was decided to replace this chamber with the spare one.
- **Cause of problems: misteering of the electron beam**


Why? Machine Protection System not sufficient enough!
Not sufficient enough interlock system based on signals from BPM, thermocouples, pressure readings based on SIP's.



Replacement of the dipole vacuum chamber in sector R1-02 - Lesson learnt

What we have learned from this accident?

- How expensive new VK2 vacuum chamber is
- How ceramic kicker chamber looks inside after 3 years of operation
- It is good to have spare parts, 13th spare dipole vacuum chamber was ready for installation
- We have the team ready to replace the damaged vacuum chamber without outsourcing support
- We have assembled with the vacuum chamber magnet for fast correct feedback system



Replacement of the dipole vacuum chamber in sector R1-02

- 13th spare dipole vacuum chamber was ready for installation
- Two vacuum sectors R1-01 and R1-02 had to be vented
- Solaris Heating Unit Controller was used to activate NEG strips in dipole vacuum chamber in sectors R1-01 and R1-02

Proceedings of IPAC18, Vancouver, BC, Canada, THPAL107

W. Kitka et al. IPAC18 Proceedings Vancouver, BC, Canada, THPAL106

„HEATING UNIT CONTROLLER AT NSRC SOLARIS”

- Whole operation took less than 2 weeks



Landau upper pick-up overheating

- Lots of HOM modes generated in the cavity
- No grids on pick-up ports—strong coupling
- Dominating frequencies around 1,5 and 1,9 GHz
- Frequent overheating of attenuators and loads
- Gas discharge tubes installed, to contain the problem
- Cable insulation melted, GDTs overheating, damaged RF N-type connector socket
- Bottom pickups do not cause any problems



Recent upgrades in the machine vacuum system

Installation of Residual Gas Analyzer

- Frond-ends: PEEM / UARPES beamlines




- Magnets R1-04 (XMCD) / R1-06 (PHELIX)



Integration of two TSP's with main cavities

Upgrade of two SIP's from Landau cavities with NEG's cartridges




Recent performance

Injection → Ramping → Decay


Unusual behavior of RF sector: pressure for electron energy 0.5 GeV is higher than for electron energy 1.5 GeV

Why? Position of the plungers




Installation of Phelix vacuum ID section & Undulator

- According to the technical specification (SIWZ) the installation of vacuum parts to be performed by Solaris with Supervision FMB
- NEG activation process has been performed by Solaris Heating Unit Controller according to guidelines provided by FMB
- Leak check and residual gas analysis at the end of the process have been fulfilled, no contamination by hydrocarbons has been detected
- Average pressure based on two SIP's at the end of the process was in range $\sim 3e-10$ mbar
- In October the Phelix undulator was installed




Installation of Pinhole diagnostic beamline

- Diagnostic beamline was designed and installed by Solaris
- Vacuum parts has been assembled and bake-out outside of the storage ring
- Vacuum criteria regarding leak check and residual gas analysis at the end of the process have been fulfilled, no contamination by hydrocarbons has been detected



100 MHz chopper in the linac in operation




chopper





Bunch train shape at the end of the linac
and in TL without chopper
Bunch train length ~ 180 ns, charge 3.6 nC
Injection efficiency up to 30%
Injection rate 1.4 mA/s

Bunch train shape at the end of the linac and in TL
with chopper
Bunch train length ~ 100 ns, charge 0.6 nC
Injection efficiency between 45-60% -linac and ring
optimisation
Injection rate 1 mA/s




Injection, LC tuning & ramping ~ 10 min
Additional time need for LC fine tuning – few min.
Beam delivered average in 20 min

$I \cdot \tau$ product with integrated current



Closed orbit and orbit correction was improved with cooperation with Ward Wurtz from CLS (Saskatoon, Canada)



Closed Orbit

**With correction
&BBA before**

**With correction
&BBA After**

x_{rms}

160 μm


0.25 μm

y_{rms}

55 μm

0.22 μm

Photon beam oscillation with temperature oscillation




Temperature oscillations in the range of 1.5-2.0 °C in the storage ring have impact on beam stability.

Photon beam stability requirements for PEEM/XAS beamline:


2 μm/8h → 50 meV/8h in a long run 50 meV/24h.

At the beginning try to obtain 5 μm/8h





Measured at XBPM1&2 in the FE







Temperature oscillation decreased to 0.6 °C



Long term beam stability – long term drift of photon beam





Landau cavities tuning-electron & photon beam profiles



**Injected current of 250mA @1.5GeV LC detuned
Plungers position 28 mm**

**Injected current of 250mA @1.5GeV LC tuned
Plungers position 65 mm**


Photon beam shape profile shape and the width dependence from the Landau tuning and beam current in the machine



Repeatability and stability

- Tuning Landau Cavities
 - Not repeatable plungers positions – improved
 - Instabilities causing uncontrolled beam losses
 - Spectrum changes with current decay
- Beam profile depends also on time
- Beam profile depends on the current in the machine
- Seems to be repeatable at the same current and plungers position


Photon beam profile evolution with a time




Undulator optimisation

- Impact on the photon beam during changing the gap
 - Correction coils matrix supplied by Kyma not working properly
 - Find the new matrix with the current setup – night shifts applying algorithm to find the best settings
 - Decreasing the disturbance from 60 μm -2 μm for the phase 0, work ongoing to minimise the effect for other phases
 - Cooperation with Hamed Tarawneh from MAXIV Lab – visit planned for end of October
 - Optimisation of the lattice with respect of ID


Photon beam distortion by EPU



Horizontal Tune Measurement



Vertical Tune Measurement



Linac and Transfer Line

- ✓ Continue with the emittance and energy spread measurements
- ✓ Continue with the optics adjustments for injection optimisation
- ✓ Chopper upgrade [waiting for electronics]
- ✓ Magnets settings optimisation at nominal energy after full conditioning and SLED tuning [future]
- ✓ Studies & optics design for the full energy linac

Storage Ring

- ✓ Beam stability improvement – insertion dev. Optimisation, LC optimisation [PRIORITY!]
- ✓ Beam dynamics with insertion devices studies
- ✓ Shunting the magnets based on LOCO [ahead]
- ✓ Nonlinear beam dynamics studies with pinger
- ✓ FOFB implementation – fast correctors procured, PS specification under preparation [in progress]
- ✓ Emittance measurements on PINHOLE beamline [in progress]
- ✓ Instabilities studies & cures [HOM couplers, BbBFeedback]

Daily operation (Injections 8:00, 16:00-18:00 ; 21:30, current between 250-300mA)

Maintenance activities during shutdowns (active plan for repair – fixing magnets connection, valves connection replacement, short circuit in PFS removal etc.)

Chopper commissioning & injector optics optimisation

- 😊 Improved injection efficiency from 30% to 45%-60% - need further work
- 😊 Decreased the electron losses and radiation level (from 14uSv/h to 0.6uSv/h)

Focus on beam stability

- 😊 Closed orbit correction improvement
- 😐 Backbone water stability improvement
- 😐 Landau cavities tuning and instabilities suppressing (ongoing)
- 😐 Suppressing impact of the UARPES EPU on the beam position (ongoing)

Installation and commissioning of the PINHOLE diagnostic beamline

Preparation for the installation of the VIS diagnostic beamline

Equipment development (tune measurement device, LLRF test stand, heating unit controller, vacuum pump station)

Recent cooperation with other labs

- National Centre of Nuclear Research, Świerk, Poland –
 - vacuum installation support,
 - magnets alignment, sag measurements and removal
 - POLFEL project – SOLARIS part of the consortium
- MAXIV Laboratory, Lund, Sweden
 - Chopper & linac optics optimisation (David Olsson)
 - Landau Cavities tuning (Ake Andersson, Teresia Olsson)
 - Contact with RF, vacuum, CS, PLC and operators groups
 - EPU optimisation (Hamed Tarawneh)
- ALBA, Barcelona, Spain
 - LLRF test and workshop for Solaris (Angela Salom)
- Canadian Light Source, Saskatoon, Canada (Ward Wurtz)
 - Orbit correction optimisation
 - LOCO measurements
 - Nonlinear optics studies with/without ID
- BESSY II HZB, Berlin, Germany
 - 7T MPW
 - Hard X-ray beamline components



Thank you !



JAGIELLONIAN UNIVERSITY
IN KRAKOW



SOLARIS
NATIONAL SYNCHROTRON
RADIATION CENTRE



National Synchrotron Radiation Center SOLARIS

Kraków, 27.11.18